



US Army Corps
of Engineers ®



Caseville Harbor, MI

Harbor Features

- Located at the mouth of the Pigeon River on the east shore of Saginaw Bay, about 17 miles southwest of Port Austin, MI
- Authorization: Rivers & Harbors Act of 23 Oct 1962
- Shallow draft recreational harbor
- Project depth of 10 feet in the entrance channel and 8 feet in the inner channel
- Over 4,000 feet of maintained federal channel
- Approximately 1,800 feet of pier
- Dredged material placed along the beach as beach nourishment
- Major stakeholders: U.S. Coast Guard, Michigan DNR, village of Caseville, and various marina owners

Project Requirements

- Approximately 10,000 to 18,000 cubic yards of material must be dredged on a 3 to 5 year cycle.
- Maintenance dredging was completed in 2019 with FY18 funds, when approximately 6,000 cubic yards of material were removed.
- Maintenance dredging is not currently required.

Consequences of Not Maintaining the Project

- Loss of local jobs
- Loss of recreational and charter fishing in the area
- Federal breakwater protects infrastructure including public boardwalk
- Potential safety issues for recreational boating community



Transportation Importance

- This project serves as an important harbor of refuge and supports charter fishing and recreational navigation interests.
- The local community has established significant infrastructure around the harbor facilities that generates income from harbor users and visitors to the area.
- Provides 200 recreational boat slips

**U.S. Army Corps of Engineers Fiscal Year (FY) 2019, 2020, and 2021
Caseville Harbor, MI - Project Requirements and President's Budget (\$1,000)**

Work Package	FY19 Requirement	FY19 Appropriation	FY20 Requirement	FY20 Appropriation	FY21 Requirement	FY21 President's Budget
Real Estate Management	0	0	0	0	6	0
TOTAL	0	0	0	0	6	0

Congressional Interests

- Representative Paul Mitchell R-MI-10
- Senator Gary Peters D-MI
- Senator Debbie Stabenow D-MI